

COPY TO:

Steve Westerman

Quantum Environmental & Engineering Services, LLC Quantum Environmental & Engineering Services, LLC. 126 Dante Road Knoxville, Tennessee 37918 Telephone (865) 689-1395 Fax (865) 689-6844 To: Tennessee Department of Environment and Conservation 3711 Middlebrook Pike Knoxville, TN 37921 Letter of Transmittal Date: 9/23/15	
☐ Shop Drawings	ations
COPIES LAST DATE NO. DESCRIPTION	
3 7/14/15 Proposed Storm Sewer Outlet – ARAP Permit application	
1 7/22/15 Aquatic Resource Alteration Permit (ARAP) application	
7 74 Augustio Flessouros Autoration Fernita (Augustion	
THESE ARE TRANSMITTED AS CHECKED BELOW: For approval	on
REMARKS:	
John,	
Please call with any questions.	

Thanks

Signed:

Joe Ferowich



TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION SEP 2 3 2015

Division of Water Resources

William R. Snodgrass Tennessee Tower, 312 Rosa L. Parks Avenue, 11th Floor, Nashville, Tennessee 37243 1-888-891-8332 (TDEC)

Application for Aquatic Resource Alteration Permit (ARAP) & State §401 Water Quality Permit

	_			` _				•
OFFICIAL STATE USE ONLY	Site #:				Permit #	:		
Section 1. Applicant Information (individual responsible for site, signs certification below)								
Applicant Name: Steven L Western	nan							
Company: Tennessee Department	of Corre	ection		Signatory'	s Title or	Position: Direc	ctor, Office of	f Facilities Planning
Mailing Address: Ground Floor, Rachel Jac	ckson Buil	ding, 320 Sixtl	Avenue North	City: Nas	hville		State: TN	Zip: 37243
Phone: (616) 741-1000	F	Fax: (616)74	1-6579	E-mail: st	even.we	esterman@	tn.gov	
Section 2. Alternate Contact/Consultan	t Informa	tion (a consu	ltant is not requ	uired)				
Alternate Contact Name: Joseph Ferd	owich,	P.E _e						
Company: Quantum Environmental & Engir	neering Se	rvices, LLC		Title or Po	sition: Pro	ject Manager		-
Mailing Address: 126 Dante Road				City: Kno	xville		State: TN	Zip: 37918
Phone: (865) 689-1395	1	ax: (865)689-	6844	E-mail:				
Section 3. Fee (check appropriate box and	d submit r	equisite fee w	ith application)					
■ No Fee Submitted	☐ Fee	Submitted wit	h Application		Amount	Submitted:	\$ <u>0</u>	
Current fee schedules for Aquatic Resourd	ce Alterat	ion Permit pro	ocessing may be	found at the	e Division	of Water Reso	urces webpage	at
http://www.tn.gov/environment/permits/ar	ap.shtml	or by calling ((615) 532-0625.	Make check	ks payable	to "Treasurer	, State of Tenn	essee".
Section 4. Project Details (fill in informa	ation and	check approp	riate boxes)					
Site or Project Name: Brushy Mountai	in State	Penitentia	ry	Nearest C	City, Town	or Major Land	dmark: Petro	os, TN
Street Address or Location: Off Highw	ay 116,	Petros, T	N *					
County/ice): Manager County			MS4 Jurisdiction:		I	Latitude (dd.dddd): 36.1013N		
County(ies): Morgan County					I	Longitude (dd.dddd): 84.4466W		
Resource Proposed for Alteration:	Stream	□ w	etland	Reservo	oir			
Name of Water Resource: Stockstill	Creek							
Brief Project Description (a more detailed	description	on is required	under Section 8	3):				
Installation of a Stormwater F	Pipe H	eadwall to	discharge	stormw	ater in	to the Cred	ek.	
Does the proposed activity require approve government agency? Yes No		e U.S. Army	Corps of Engine	eers, the Ten	nessee Va	lley Authority	, or any other fo	ederal, state, or local
If Yes, provide the permit reference numb	ers: '							

Is the proposed activity associated with a	_	-	•					
If Yes, submit site plans and identify the l							Plans attached	
If applicable, indicate any other federal, st the past (i.e. construction general permit c				the overall p	roject site	(common plai	n of developme	nt) has obtained in
N/A								
Section 5. Project Schedule (fill in inform	nation and	d check appro	priate boxes)					
Start date: August 15, 2015		Estimated e	end date: Aug	ust 30,20	15			
Is any portion of the activity complete now? Yes No If yes, describe the extent of the completed portion:								

Application for Aquatic Resource Alteration Permit (ARAP) & State §401 Water Quality Permit

The required information in Sections 6-11 must be submitted on a separate sheet(s) and submitted in the same numbered format as presented below. If any question in not applicable, state the reason why it is not applicable.

Sectio	n 6. Project Description		ched
6.1	A narrative description of the scope of the project	Yes	No
6.2	USGS topographic map indicating the exact location of the project (can be a photographic copy)	•	
6.3	Photographs of the resource(s) proposed for alteration with location description (photo locations should be noted on map)	▣	
6.4	A narrative description of the existing stream and/or wetland characteristics including, but not limited to, dimensions (e.g., depth, length, average width), substrate and riparian vegetation		
6.5	A narrative description of the proposed stream and/or wetland characteristics including, but not limited to, dimensions (e.g., depth, length, average width), substrate and riparian vegetation	• •	
6.6	In the case of wetlands, include a wetland delineation with delineation forms and site map denoting location of data points		
6.7	A copy of all hydrologic or jurisdictional determination documents issued for water resources on the project site		•
Section	7. Project Rationale	Atta Yes	ched No
	be the need for the proposed activity, including, but not limited to, the purpose, alternatives considered, and what will be done to a minimize impacts to streams or wetlands.	ِ •	
Section	8. Technical Information	Atta Yes	ched No
8.1	Detailed plans, specifications, blueprints, or legible sketches of present site conditions and the proposed activity. Plans must be 8.5.x 11 inches. Additional larger plans may also be submitted to aid in application review. The detailed plans should be superimposed on existing and new conditions (e.g., stream cross sections where road crossings are proposed)	⊡	
8.2	For both the proposed activity and compensatory mitigation, provide a discussion regarding the sequencing of events and construction methods	▣	
8.3	Depiction and narrative on the location and type of erosion prevention and sediment control (EPSC) measures for the proposed alterations	⊡	
Section limitati	9. Water Resources Degradation (degree of proposed impact) Note that in most cases, activities that exceed the scope of the Goons are considered greater than de minimis degradation to water quality.	eneral P	ermit
My act	vity, as proposed:		
a.	■ Will not cause measurable degradation to water quality		
b.	☐ Will only cause de minimis degradation to water quality		
c.	Will cause more than de minimis degradation to water quality (Complete additional sections 9-11)		
d.	☐ Unsure/need more information		
Tenness	ormation and guidance on the definition of de minimis and degradation; refer to the Antidegradation Statement in Chapter 0400-40 see Water Quality Criteria Rule: https://www.tn.gov.sos.rules-0400-0400-40-03-20131216.pdf . For more information on seneral Permits can cover, refer to the Natural Resources Unit webpage at http://www.tn.gov.environment-permits-arap.shtml	-0306 (specifics	of the on
If you c	hecked "c." above in Section 9, complete the following 2 sections, 10-11.		
Section	10 Detailed Alternative Analysis	Attac	hed

Section	Section 10. Detailed Alternative Analysis		Attached	
	T	Yes	No	
10.1	Analyze all reasonable alternatives and describe the level of degradation caused by each of the feasible alternatives			
10.2	Discuss the social and economic consequences of each alternative			
10.3	Demonstrate that the degradation associated with the preferred alternative will not violate water quality criteria for uses designated in the receiving waters, and is necessary to accommodate important economic and social development in the area			

CN-1091 (Rev. 1-15) (Page 2 of 3)

Application for Aquatic Resource Alteration Permit (ARAP) & State §401 Water Quality Permit

Sectio	n 11. Compensatory Mitigation	Atta Yes	ched No
11.1	A detailed discussion of the proposed compensatory mitigation		
11.2	Describe how the compensatory mitigation would result in no net loss of resource value		
11.3	Provide a detailed monitoring plan for the compensatory mitigation site	o o	
11.4	Describe the long-term protection measures for the compensatory mitigation site (e.g., deed restrictions, conservation easement)		
Certifi	cation and Signature		
proprie	lication submitted by a corporation must be signed by a principal executive officer; from a partnership or proprietorship, by the part tor respectively; from a municipal, state, federal or other public agency or facility, the application must be signed by either a principal ranking elected official, or other duly authorized employee.	tner or pal execu	itive
inform false in	ify under penalty of law that this document and all attachments were prepared by me, or under my direction or supervision. The ation is to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for formation, including the possibility of fine and imprisonment. As specified in Tennessee Code Amotated Section 39-16-702(a) (a) (a) (b) is made under penalty of perjury.	submitti	ed ng

Submitting the form and obtaining more information Note that this form must be signed by the principal executive officer, partner or proprietor, or a ranking elected official in the case of a municipality; for details see Certification and Signature statement above. For more information, contact your local EFO at the toll-free number 1-888-891-8332 (TDEC). Submit the completed ARAP Application form (keep a copy for your records) to the appropriate EFO for the county(ies) where the ARAP activity is located, addressed to Attention: ARAP Processing. You may also electronically submit the complete application and all associated attachments (e.g., maps, wetland delineations and narrative portions) to water permits a transport.

Official Title

7-22-15

EFO	Street Address	Zip Code	EFO	Street Address	Zip Code
Memphis	8383 Wolf Lake Drive, Bartlett	38133-4119	Cookeville	1221 South Willow Ave.	38506
Jackson	1625 Hollywood Drive	38305-4316	Chattanooga	1301 Riverfront Pkwy., Ste. 206	37402
Nashville	711 R S Gass Boulevard	37243	Knoxville	3711 Middlebrook Pike	37921
Columbia	1421 Hampshire Pike	38401	Johnson City	2305 Silverdale Road	37601



OFFICIAL STATE USE ONLY

Printed Name

Received Date:	Permit Number: Reviewer:			Field Office:	
Fee amount paid:	T & E Aquatic Flora and Fauna:		Impaired Receiving Stream:	Application Rev	iew:
Date:				Deficient	Date:
Check#:	Exceptional TN Water:			Complete	Date:

Stormwater Outfall Installation

At The

Existing Wastewater Treatment Plant

For The

Former Brushy Mountain Detention Facility

Located In Petros, Tennessee

Morgan County

Supplement to the Aquatic Resource Alteration Application

Sections 6 through 11

Date: July 21, 2015


Owner: Tennessee Department of Correction 6th Floor Rachel Jackson Building 320 Sixth Avenue North Nashville, Tennessee 37243

Prepared By: Quantum Environmental & Engineering Services

120 Dante Road

Knoxville, Tennessee 37918

Phone: 865-689-1395



INDEX

Section 6: P	roject Description
6.1	Project Description
6.2	USGS Topographic Map
6.3	Photographs of the Existing Creek
6.4	Narrative Description of the Existing Creek 6
6.5	Narrative Description of the Proposed Creek 6
6.6	Wetlands Delineation 6
6.7	Hydrologic /Jurisdictional Determination Documents 6
Section 7: P	roject Rationale
7.0	Narrative 7
Section 8: To	echnical Information
8.1	Detailed Plans and Specifications 8-9
8.2	Construction Sequence
8.3	Depiction and Narrative of Proposed Erosion Prevention and
	Sediment Control Measures 10-11
Section 0: M	/ater Pesources Degradation


Section 6: Project Description

6.1 Project Description

The purpose of the subject permit request is to install a storm sewer outfall into Stockstill Creek adjacent to the existing wastewater treatment plant that previously served the former Brushy Mountain Detention Facility. This request has resulted from the proposed decommissioning of the existing wastewater treatment plant and the wastewater collection system for the former Brushy Mountain Detention Facility. The plant is located on Highway 116, just south of the entrance to the former Brushy Mountain Detention Facility grounds. The wastewater treatment plant currently is permitted to discharge treated wastewater into Stockstill Creek. The Detention Facility has been closed for several years and it has been determined that the wastewater treatment plant is no longer necessary. It has also been determined through detailed engineering studies, that the existing wastewater collection system has excessive stormwater inflow and infiltration into the system. It is not cost effective to repair the system; therefore, the collection system will be disconnected from the wastewater treatment plant and converted into a storm sewer. All existing sanitary sewer services that previously discharged to the collection system have been disconnected. In addition, in accordance with a request from the local TDEC field office, stormwater samples have been taken from the collection system and tested for applicable contaminants such as coliform. The samples have been determined to be negative; therefore, the system is now ready to be disconnected from the treatment plant and routed directly to Stockstill Creek. The proposed stormwater outfall will consist of a concrete headwall for a twelve inch diameter high density polyethylene pipe, located just outside the bank of the creek. Rip rap will be placed at the outlet of the headwall to prevent erosion.

6.2 USGS Topographic Map






Center: 36.1013°N 84.4466°W


Elevation at center: 1,394 feet (425 meters)


Quad: USGS Petros Drg Name: o36084a4 Drg Source Scale: 1:24,000


LOCATION MAP


6.3 Photographs of the Existing Creek











6.4 Narrative Description of the Existing Creek

The existing creek is approximately 10 feet wide and had a flow depth of approximately 6-inches at the time of this narrative (June 6, 2015). The bottom of the creek consisted of a clay and rubble bottom, with small boulders spread through-out the creek. The sides of the creek had a slope of approximately 1:1 on the near side of the creek and approximately 3:1 on the far side of the creek. There was no vegetation within the creek; however, there was a mixture of grass and weeds along both sides of the creek.

6.5 Narrative Description of the Proposed Creek

There will be no change to the existing creek, other than a cut in the creek bank to allow the new stormwater outfall to enter the creek. The flow energy will be mitigated with rip rap so that the new stormwater flow enters the creek at a non-erosive velocity.

6.6 Wetlands Delineation

There are no wetlands associated with the subject site.

6.7 Hydrologic/Jurisdictional Determination Documents

There are no hydrologic or jurisdictional determination documents associated with the subject project.

Section 7: Project Rationale

7.0 Narrative

The existing sanitary sewer collection system was installed to serve the former Brushy Mountain Detention Facility. The system is very old and experiences significant stormwater inflow and infiltration. An engineering study was performed to evaluate the condition of the collection system, and it was determined that it was not cost effective to repair the system. It has also been determined that the wastewater treatment plant serves no useful purpose; therefore, it is going to be decommissioned. As part of the decommissioning of the plant, the wastewater collection system is to be disconnected from the wastewater treatment plant to eliminate the stormwater flows into the plant. The stormwater flowing into the system will then need to be discharged to the creek.

The alternative to discharging the collection system into the creek, would be to fill the existing sewer lines and manholes with flowable fill to close the system and eliminate all stormwater flows. This alternative would also eliminate the potential for the system to provide a useful purpose to the area, which is collection of stormwater flows to eliminate potential drainage issues in the redevelopment of the Detention Facility grounds. It is currently proposed to develop a distillery within the old prison walls, and construct a restaurant and gift shop in several other buildings on the prison grounds. As this area develops, the existing wastewater collection system will be a valuable asset to provide off-site drainage of stormwater flows.

Section 8: Technical Information

8.1 Detailed Plans and Specifications

Refer to the following pages for detailed plans and specifications.

8.2 Construction Sequence

The decommissioning of the wastewater treatment plant and the subject wastewater collection system has already begun. All existing services to the collection lines have been disconnected, and the first round of stormwater sampling has been completed. The results of these samples came up negative for all contaminants of concern. Another round of sampling is currently scheduled, and should be completed by the time this ARAP application is received for review.

Upon approval of the ARAP Permit, the Department of Correction will disconnect the collection system piping from the wastewater treatment plant and install a new 12- inch diameter HDPE pipe toward Stockstill Creek. The pipe will not extend into the creek, but rather, it will end outside the banks of the creek, and a concrete headwall will be installed on the end of the pipe. A swale will be excavated through the bank of the creek to allow the stormwater to drain into the creek. This work will all be done in the "dry" to prevent erosion and the discharge of any muddy water into the creek. The swale will be lined with geotextile fabric and covered with rip rap. The sides of the swale above the flow line will be covered with an erosion control fabric and seeded.

8.3 Depiction and Narrative of Erosion Prevention and Sediment Control Measures

The proposed erosion prevention and sediment control measures are illustrated on the attached plan sheets. In summary, the proposed measures will include temporary and permanent measures. The temporary measures required are minimal as this is a linear construction project which will be completed within one work day. The primary concern is to do the work in the "dry", which can be achieved by starting work on a day when there has been no rain for at least 24 hours. If necessary, existing stormwater flow in the collection system will be collected in a lined sump and pumped around the construction area.

The permanent measures include the geotextile fabric and rip rap in the drainage swale to the creek, and the lining of the sideslopes with erosion control fabric and seeding. The fabric will be staked into the slope to prevent failure during storm events prior to the grass taking hold. The area of the pipe trench will be graded, seeded and mulched.

Section 9: Water Resources Degradation

Refer to the Permit Application Form